BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK DIV/E-PMT/01/2013-14 Dated: 01-09-2013

APPROVED TENDER SCHEDULE -'B'

Item No: 6

Name of Work: -Providing Asphalting to AD colony main road in ward No-02 of yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S Nalaraj	
				Rate	Rate in Words
1	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	137.20	141.00	Rupees one hundred forty one only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing lipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 141 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	137.20	70 00	Rupees seventy only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 180kgs. with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	27.90	4200.00	Rupees four thousand two hundred only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri H S Nataraj	
				Rate	Rate in Words
4	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs. with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplasiesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	43.67	5300.00	Rupees five thousand three hundred only
5	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, lying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Quintal	34.87	7500.00	Rupees seven thousand five hundred only
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,billresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	261.00	255.00	Rupees two hundred fifty five only
7	RCC Precast covering slab for drain (10cm thick) with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	70.50	1240.00	Rupees one thousand two hundred forty only
8	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete for R.C.C works laid in 15cms thick layers and well compacted vibrating curing etc, smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for Beams, column, Staircase and Roof with M-20(cement -320 Kg/Cum) with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	10.00	5700.00	Rupees five thousand seven hundred only
9	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. do- for concrete pavement with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Rmt	35.00	113.00	Rupees one hundred thirteen only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor / Approved Rates Sri H. S Nalera	
				Rate	Rate in Words
10	KSRRB 300- Scarifying the surface and dressing KSRRB 300-44: Scarifying top bituminous surface or surface dressing or premix carpet including picking up scarified materials, stacking of Id serviceable materials within a lead of 100 meters by manual means including cost of all labour charges complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	1170.00	18.00	Rupees eighteen only
11	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of lipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	175.50	1108.00	Rupees one thousand one hundred eight only
12	KSRRB M500-6: providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	1170.00	44.00	Rupees forty four only
13	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing and average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.6 complete in all respects as per specifications with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	29.25	9100.00	Rupees nine thousand one hundred only

Signature of the Contractor

Executive Engineer
Bagalakunte Division,
BBMP, Bangalore-24

ಇಂತಿ ತಮ್ಮ ವಿಶ್ವಾಸಿ,